

Fire Testing Laboratories

Fire Test Report

Report Number: F-11-030-9

Date: April 19, 2011

Page 1 of 4

Title: Surface Burning Characteristics of Whisper Walls

PCAS No.: 01TTIAH02888

Tested by: D. Sandoval

D. Fast

Reported by: /

Diane Sandoval Fire Test Laboratory Lead **Product Testing Laboratories** Requested by: E. Williams

Distribution:

E. Williams

Introduction

One acoustical panel system was submitted by E. Williams, and was tested for flame spread and smoke development in accordance with ASTM test method E84 - 10a "Standard Test Method for Surface Burning Characteristics of Building Materials." The testing of panel system samples was performed by D. Sandoval and D. Fast on April 13-15, 2011 at the Johns Manville Technical Center located at 10100 West Ute Avenue, Littleton, Colorado.

Sample Description

Test Sample #9 – Whisper Walls WhisperTak Panel

Whisper Walls 3/4" self supporting WhisperTak tack panel stretching system framed around a 1/2" Acoustitherm tackable core and covered with a Whisper Walls 100% polyester fabric stretched over the surface.



NATIONAL VOLUNTARY LABORATORY ACCREDITATION PROGRAM FOR SELECTED TEST METHODS FOR THERMAL INSULATIONS.

NOTE: THE CONTENT OF THIS REPORT RELATES ONLY TO THE ITEMS TESTED AND THIS REPORT SHALL NOT BE REPRODUCED EXCEPT IN FULL WITHOUT THE PRIOR CONSENT OF THE ISSUING LABORATORY. USE OF THIS REPORT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY NVLAP, NIST, OR ANY AGENCY OF THE FEDERAL GOVERNMENT IS PROHIBITED.



Fire Testing Laboratories

Fire Test Report

Report Number : F-11-030-9

Date: April 19, 2011

Page 2 of 4

Test Method

ASTM test method E84 - 10a "Standard Test Method for Surface Burning Characteristics of Building Materials."

ASTM E84 Section 7.0 Calibration - Select red grade oak sample was tested on February 3, 2011 and documented in Fire Test Report # F-11-011CAL.

Section 7.1 Fiber Cement Board (1/4" thick) was placed in position on the underside of the lid.

Section 7.2 Tunnel draft: 0.15 inches of H_2O

Section 7.3 Main draft: 0.055 and 0.100 inches of H_2O

Air Velocity: 240 ± 5 ft/minute

Section 7.4 Conditions of the test room are maintained at 73.4 ± 5 degrees F and 50% rH

Section 7.8 Time for flame to reach the end of the red oak specimen 19.2 ft. may not exceed

.5 min \pm 15 seconds. The results of the testing were a flame spread index of 91.4 and a smoke developed index of 106.5. This occurred at 5.3 minutes for this calibration which is within the 5 minute and 30 second requirement \pm 15 seconds.

These values were calculated in accordance with the test method by calculating the area under the curves for both flame spread and photocell measurement systems.

Another criteria used for determining when the flame has reached the end point is when the thermocouple at 23 feet reaches 980 F. This occurred at 5.2 minutes during this calibration which is outside the specification.

*Exception to the method – Section 5.1.8.3 The exhaust system is to be insulated with at least 2 inches of high temperature mineral composite material from the exhaust end of the fire chamber to the photometer location. Due to recent checks of the duct system, 2 sections of the exhaust are not insulated at this time.

Test Procedure

Test Specimen Mounting:

The underside of the lid was covered with ¼ inch cement board held in place with binder clips. The samples were installed in 3 - 8 foot sections butted together at the ends and mounted below the lid of the tunnel, and were self supporting.



PROHIBITED.

NATIONAL VOLUNTARY LABORATORY ACCREDITATION PROGRAM FOR SELECTED TEST METHODS FOR THERMAL INSULATIONS.

NOTE: THE CONTENT OF THIS REPORT RELATES ONLY TO THE ITEMS TESTED AND THIS REPORT SHALL NOT BE REPRODUCED EXCEPT IN FULL WITHOUT THE PRIOR CONSENT OF THE ISSUING LABORATORY. USE OF THIS REPORT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY NVLAP, NIST, OR ANY AGENCY OF THE FEDERAL GOVERNMENT IS



Fire Testing Laboratories Fire Test Report

Report Number: F-11-030-9

Date: April 19, 2011

Page 3 of 4

Specimen Testing - Using the same settings used for the red oak calibration standard, the preheat sequence was completed, the samples loaded into the tunnel and the test was run monitoring the distance that the flame front travels across the specimen.

Results

The results of these tests are given below. The test method requires that flame spread must be reported by rounding to the nearest multiple of 5. The method also requires that smoke development also be reported rounding to the nearest multiple of 5 unless the smoke development index is 200 or more, which would round smoke development to the nearest 50 points. Data from the test is shown in the results table included in this report

Results Summary:

Sample ID	Test Side	Test Support Materials	Construction Materials	Flame Spread Index	Smoke Developed Index	Rounded Values
Surface Burn Test 9	Fabric	Self supporting 2' x 8'	Whisper Walls Test Sample #9	12.5	74.1	15/75



NATIONAL VOLUNTARY LABORATORY ACCREDITATION PROGRAM FOR SELECTED TEST METHODS FOR THERMAL INSULATIONS.

NOTE: THE CONTENT OF THIS REPORT RELATES ONLY TO THE ITEMS TESTED AND THIS REPORT SHALL NOT BE REPRODUCED EXCEPT IN FULL WITHOUT THE PRIOR CONSENT OF THE ISSUING LABORATORY. USE OF THIS REPORT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY NVLAP, NIST, OR ANY AGENCY OF THE FEDERAL GOVERNMENT IS PROHIBITED.



Fire Testing Laboratories Fire Test Report

Report Number: F-11-030-9

Date: April 19, 2011

Page 4 of 4

Results Table 1:

I	la a made -!	Funnel Te	- Tunn - I P		
rning C	narateristics	s in a 25 Fc	ot Tunnel Furna	ice	
			T	1 102000 C	
	 				
	-				minutes
\rightarrow			lested:		
	ļ		<u> </u>	12:48 PM	
	1				
	·[,		
68.4	cu. ft.		Operator:	D. Sandoval	
6.8	cfm		Requestor:	E. Williams	
2.5	ft.				
12.5	T	-			
74.1				1	l
	1		T	1	<u> </u>
	,		'		
$\overline{}$	محسمي		1		Ì
المستمسم					
		+		── Test-San	ple
				Red-Oak	<u> </u>
				—	
4		6	8	10	
					ļ
	+		-		ļ
- 1	į		1	·	
					ļ
		i			
	 		-		
					1
	+			Red Oak	
	<u></u>				
		 			
	4	ь	a	10	1
- 1	1		T	1	1
	1				1
'			•		
	1				1
	+	_			
					
				Test San	nole
				1631 0411	17.0
					
	+	-+-	 		
	4	6	8	10	<u> </u>
	Minutes				· ·
	68.4 6.8 2.5 12.5 74.1	68.4 cu. ft. 6.8 cfm 2.5 ft. 12.5 74.1	68.4 cu. ft. 6.8 cfm 2.5 ft. 12.5 74.1	Test Number: Test Duration: Tested: 68.4 cu. ft. Operator: 6.8 cfm Requestor: 12.5 ft. 14.1 6 8	Test Number: AH02888-9 Test Duration: 10.00 Tested: 4/15/2011 12:48 PM 68.4 cu. ft. Operator: D. Sandoval 6.8 cfm Requestor: E. Williams 2.5 ft. 12.5 74.1



NATIONAL VOLUNTARY LABORATORY ACCREDITATION PROGRAM FOR SELECTED TEST METHODS FOR THERMAL INSULATIONS.

NOTE: THE CONTENT OF THIS REPORT RELATES ONLY TO THE ITEMS TESTED AND THIS REPORT SHALL NOT BE REPRODUCED EXCEPT IN FULL WITHOUT THE PRIOR CONSENT OF THE ISSUING LABORATORY. USE OF THIS REPORT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY NVLAP, NIST, OR ANY AGENCY OF THE FEDERAL GOVERNMENT IS PROHIBITED.